

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 9/24/2014

CORNER DESIGNATION: R-11, Section Quarter Corner common to Sections 21, and 28
Township 6 North, Range 37 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams, Contract No. 176, dated July 20, 1872. His notes state
"Set post & marked stone mound & pits for ¼ sec cor."

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N
LS 02820
S 21
S 28
R37E
12/2014

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½" brass cap on 1½" galvanized iron pipe, 6" above ground from
which set:

- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N55°W, 15.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N66°E, 15.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S44°E, 15.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S47°W, 15.00 feet distance.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 850696.48
E = 8788054.28

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Cory A. West



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015