

A fence corner post with bird house bears S60°E 1.5 feet painted and marked.

A 24 inch diameter Ponderosa Pine blazed, scribed tagged and painted bears N65°E 131.7 feet marked T6NR37E ¼ S23 BT

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 851213.24

E = 8798352.15

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez
Corey A. West
Timothy K. Bannister



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/09/2014

CORNER DESIGNATION: R-19, Quarter Corner for Sections 23 and 26, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams in 1872 his notes state "Set rock 6x10x16 in mound of rock with pits for ¼ section corner.

BLM Cadastral Surveyor C. Alfred White in 1965 stated in his notes: The ¼ sec. cor. of secs. 23 and 26, monumented with original basalt stone, 16 x 12 x 6 ins., marked ¼ on one face, lying in a rock crib, 4 ft. square, 2 ft. high at the cor. of wire fences which bear irregularly N. 10° E., S., and W. from this point.

At the corner point

Set an iron post, 28 ins. long 2½ ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 2½ ft. base, to top, with a brass cap marked

¼ S23
S26
T6N R37E
1965

No trees available.

The corner is located at the NE. corner of the rock crib.

Surveyor Paul W.P. Tomkins noted in his February 15, 1996 survey, shown on Umatilla County Survey record of surveys 99-121-B, "North ¼ Corner of Section 26, and South ¼ Corner Section 23. History: Corner was originally established in 1872, by George Williams, U.S. Deputy Surveyor, under contract No. 176, as a rock 6x10x16, mound of rock, with pits. The BLM (Bureau of Land Management) in 1965 restored the 1872 survey by George Williams by setting for the corner a brass cap stamped "¼ S23/26 T 6N, R 37E 1965" in mound of stone 4' square and 2' high, original basalt stone marked ¼ on one face lying in rock crib. Evidence found: A brass cap stamped "¼ S23/26 T 6N, R 37E 1965" protruding 8" above ground, fence corner to South and West 4' southwest. Corner Perpetuation: None.

MOUNUMENT AND ACCESSORIES FOUND:

Found a 3½ BLM brass cap on a 2½ inch iron pipe marked ¼ S23 and S26 1965, in the ground, next to a fence corner crib, from which a fence line runs S10°E and N75°W.

MOUNUMENT MARKING DETAIL:



MOUNUMENT AND ACCESSORIES SET:

A ½ inch iron rebar and red cap +/- .3 feet above ground along NW fence line bears N86°W 33.1 feet, with attached bearing tag.

A ½ inch iron rebar and red cap +/- .3 feet above ground along SE fence line bears S0°W 19.9 feet, with attached bearing tag

A 5/8" x 30" iron rebar with cap, 5" above ground, bears S. 58° E., 15.05 ft., with a "T" post and bearing tag as witness point.