

**OREGON CORNER RESTORATION FORM**

**COUNTY:** Umatilla    **DATE:** 1/8/2015

**CORNER DESIGNATION:** R-3, Section Quarter Corner common to Sections 19, and 30  
Township 6 North, Range 37 East, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by George Williams, Contract No. 176, dated July 20, 1872. His notes state  
"Set post marked stone & pits for 1/4 Sec Cor."

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found

**MOUNUMENT MARKING DETAIL:**

LS 02820  
T6N R37E  
1/4  $\frac{S 19}{S 30}$   
1/2015

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set a 2 1/2" brass cap on a 1 1/2" galvanized iron pipe, 3" below ground  
surface stamped, T6N R37E S19 S30 1/2015 LS02820 from which set:

A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N24°W, 13.50 feet distance.

A 26" diameter locust tree, bears N82°E, 32.50 feet distance.

An 18" diameter locust tree, bears S19°E, 87.10 feet distance.

A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S38°W, 10.00 feet distance.

**LOCATION AND COMMENTS:**

Corner falls 10 ft. W. of the center of the road and 7.5 ft. of a N. – S. fence. Bearings taken with  
Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 850332.80

E = 8777665.42

**COMPASS DECLINATION:** 15° East

**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group

5 N. Colville, Suite 200


Walla Walla WA 99362

**WITNESSES:** Thomas J. Boshart

Felipe G. Hernandez



*Greg E. Flowers*



RENEWS 12/31/15

06/29/2015