


COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 6/26/2014

CORNER DESIGNATION: R-7, Section Quarter Corner common to Sections 20, and 29 Township 6 North, Range 37 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams, Contract No. 176, dated July 20, 1872. His notes state "Set stone 4 x 6 x 15 mound & pits for ¼ Sec Cor."

Surveyor Paul W.P. Tomkins noted in his January 8, 2005 survey, shown on Umatilla County Survey Record of Plats 2005-02, "Attached sign to fence post N31°W, 23.5' from Corner. Set Rebar and yellow cap 1 ft. deep for proportioned ¼ Corner."

Surveyor Paul W.P. Tomkins noted in his October 14, 2008 survey, shown on Umatilla County Survey Record of Plats 2008-29, "5/8" Rebar with yellow cap 43ft. east of fence line at S ¼ Corner S.12, per Partition Plat 2005-02."

MOUNUMENT AND ACCESSORIES FOUND:

Found at Quarter Corner for common Secs 20 & 29, a 5/8" x 30" iron rebar with yellow plastic cap "Tomkins Surveying" +/- 1 foot deep in open grassy area.

Found a fence corner post bears N30°W, 23.50 feet distance, with no sign or other markings visible.

A N-S barbed wire fence is +/- 10.80 west of the corner.

MOUNUMENT MARKING DETAIL:

T6N R37E

S 20 ¼

S 29

2014

LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the position of the found 5/8" iron rebar, set a 1½" x 30" galvanized iron pipe with 2½" brass cap stamped, T6N R37E S20 S29 2014 LS02820 set 18 inches below surface from which set:

A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N30°W, 25.00 feet distance, set +/- 1 foot north of fence corner post.

A "Deep 1" silver magnet buried 18 inches deep, bears N36°E, 14.25 feet distance.

A "Deep 1" pink magnet buried 18 inches deep, bears S60°E, 11.80 feet distance.

A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S24°W, 24.50 feet distance, set along fence line with a T-post.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 850519.22

E = 8782904.57