

**OREGON CORNER RESTORATION FORM**

**COUNTY:** Umatilla    **DATE:** 12/31/2014

**CORNER DESIGNATION:** V-11, Quarter Corner for Sections 28 and 33, Township 6 North, Range 37E, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 8"x8"x12" mound and pits for quarter section corner to Sections 28 & 33.

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found.

**MOUNUMENT MARKING DETAIL:**

T6N R37E  
    S28        1/4  
    S33  
12/2014  
LS 02820

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set a 2 1/2 inch brass cap on 1 1/2" galvanized iron pipe, two inches above ground marked 1/4 corner of Sections 28 and 33, T6N,R37E by LS 02820 on 12/ 2014, From which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N52°W, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N45°E, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S42°W, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S47°E, 10.00 feet.

**LOCATION AND COMMENTS:**

No trees nearby a fence running northeasterly with a tack road running along it, is west of the corner 140 ft., track road runs parallel to fence N-S, 12' East right to point. Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 845519.11  
E = 8788223.35

**COMPASS DECLINATION:** 15° East


**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Joseph R. Latimer  
Corey A. West



*Greg E. Flowers*



RENEWS 12/31/15

*06/29/2015*

*15-063-C*