

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 12/19/2014

CORNER DESIGNATION: V-13, Corner for Sections 27, 28, 33 and 34, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post and stone mound and pits for corner of Sections 27, 28, 33 & 34.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N R37E
S27 | S28
S33 | S34
12/2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2 1/2 inch brass cap on 1 1/2" galvanized iron pipe, 6" above ground marked corner of sections 27,28, 33 and 34, T6N,R37E by LS 02820 on 12/ 2014, From which:
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N43°W, 15.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S42°W, 18.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS=HDJ" bears N48°E, 10.00 feet.
A six inch diameter fir tree bears S27°E 29.60 feet blazed, scribed and tagged accordingly.

LOCATION AND COMMENTS:

Corner falls on steep west facing slope with three foot tall shrubs. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 845614.87
E = 8790814.13

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Corey A. West



RENEWS 12/31/15

06/29/2015