

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/02/2014

CORNER DESIGNATION: V-23, Quarter Corner Section for Sections 25 and 36, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams in 1872 his notes state "Set post for quarter section corner to Sections 25 & 36 from which"

- A White Fir 8 inch diameter bears N10°W 29 links distance.
- A Tamarack 14 inch diameter bears S42°W 26 links distance.

MOUNUMENT AND ACCESSORIES FOUND:

No Evidence Found

MOUNUMENT MARKING DETAIL:

1/4 T6N
 S25 R37E
 S36
 2014
 LS 02820

MOUNUMENT AND ACCESSORIES SET:

- At the surveyed position, set a 1½" x 30 galvanized iron pipe with a 2½ brass cap, marked quarter corner for sections 25 and 36, T6N, R37E by LS 02820 2014, from which:
- A 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N60°E, 32.15 feet.
- An 11 inch in diameter White Fir, bears N65°W, 8.60 feet, blazed, scribed and tagged.
- A 24 inch in diameter White Fir, bears S22°W, 48.60 feet, blazed, scribed and tagged.
- A 12 inch in diameter White Fir, bears S32°E, 22.50 feet, blazed, scribed and tagged.

LOCATION AND COMMENTS:

Moderate south facing hill with heavy timber. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 846192.78
E = 8803809.42

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Justin M. Koeberle
Felipe G. Hernandez



RENEWS 12/31/15

06/29/2015