

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 01/08/2015

CORNER DESIGNATION: V-3, Quarter Corner for Sections 30 and 31, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post and mound and pits for quarter section corner to Sections 30 & 31.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N R37E
 S30 1/4
 S31
1/2015
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2 1/2 inch Brass Cap on 1 1/2"galvanized iron pipe, four inches above ground marked 1/4 corner of Sections 30 and 31, T6N,R37E by LS 02820 on 1/2015, from which:
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N32°W, 7.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N61°E, 24.20 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S42°W, 9.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S54°E, 6.00 feet.

LOCATION AND COMMENTS:

Located in heavy brush, on NE facing slope. No good bearing trees. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 845100.96
E = 8777812.38

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Corey A. West



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

15-063-C