

**OREGON CORNER RESTORATION FORM**

**COUNTY:** Umatilla    **DATE:** 01/08/2015

**CORNER DESIGNATION:** V-5, Corner for Sections 29, 30, 31 and 32, Township 6 North, Range 37E, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post, mound and pits for corner to Sections 28, 29, 32 & 33.

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found.

**MOUNUMENT MARKING DETAIL:**

T6N R37E  
S30 | S29  
S31 | S32  
1/2015  
LS 02820

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set a 2 1/2 inch Brass Cap on 1 1/2" galvanized iron pipe, three inches above ground marked corner of sections 28,29, 32 and 33, T6N,R37E by LS 02820 on 12/ 2014, from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N40°W, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N56°E, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S48°W, 12.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S21°E, 16.00 feet.

**LOCATION AND COMMENTS:**

Track road approximately 120 feet N to NE, no trees, good dirt. Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**


N = 845202.75  
E = 8780412.78

**COMPASS DECLINATION:** 15° East

**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Joseph R. Latimer  
Corey A. West



RENEWS 12/31/15

06/29/2015