

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 07/09/2014

CORNER DESIGNATION: X-17, Quarter Corner for Sections 34 and 35, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 18"x15"x10" with mound of rock for quarter sections 34 & 35.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N
¼ S34|S35
R37E
2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position set a 2½" brass cap on 1½ x 30" galvanized iron pipe, marked quarter corner for sections 34 and 35, T6N, R37E by LS 02820 2014. From which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N63°W, 41.10 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N46½°E, 32.60 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S49°W, 31.30 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S64°E, 48.20 feet.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 843293.11
E = 8795999.45

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Mark F. Wendover
Felipe G. Hernandez



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15
06/29/2015