

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 6/30/2014

CORNER DESIGNATION:

Z-13, Section Corner common to Sections 33 and 34 Township 6 North, Range 37 East and Sections 4 and 3, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set post for Sections 34, 33, 4 & 3 on a steep hill side facing the southwest, made mound of stone per instructions."

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N
S33|S34 R37E
S4|S3
T5N
2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap stamped as Corner common to Sections 33 and 34 Township 6 North, Range 37 East and Sections 4 and 3, Township 5 North, Range 37E, in 2.00 feet deep hole in bedrock. Monument is .80 feet above ground with rock mound from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N51°W, 37.68 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N66°E, 25.95 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S45°E, 35.02 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S80°W, 30.75 feet.

LOCATION AND COMMENTS:

Corner is on a southwest facing slope. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 840456.08
E = 8790915.36

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group

5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Justin M. Koberle
Felipe G. Hernandez



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015