

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 7/01/2014

CORNER DESIGNATION:

Z-15, Quarter corner common to Section 34 Township 6 North, Range 37 East and Section 3, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set quarter section post on steep hill side, facing the West."

MOUNUMENT AND ACCESSORIES FOUND:

Found post in a mound of stone, accepted as best evidence of quarter corner.

MOUNUMENT MARKING DETAIL:

 T6N
¼ $\frac{S34}{S3}$ R37E
 2014 T5N
 LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the position of the fence post, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap stamped as the quarter corner common to Section 34 Township 6 North, Range 37 East and Section 3, Township 5 North, Range 37E, from which:
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N55°W, 20.85 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N8°E, 45.13 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S57°E, 23.15 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S33°W, 15.80 feet.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:


N = 840572.54
E = 8793501.06

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Justin M Koberle
Felipe G. Hernandez



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15
6/29/2015