

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 7/01/2014

CORNER DESIGNATION:

Z-7, Quarter corner common to Section 32 Township 6 North, Range 37 East and Section 5, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set quarter section post on west side of ravine coarse NE 40, drove charred stake, dug pits and raised mound as per instructions."

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N
¼ $\frac{S32}{S5}$ R37E
2014 T5N
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap stamped as the quarter corner common to Section 32 Township 6 North, Range 37 East and Section 5, Township 5 North, Range 37E, from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N86°W, 22.13 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N53°E, 18.41 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S57°E, 27.06 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S13°W, 24.02 feet.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 840108.78
E = 8783158.27

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Justin M Koberle
Felipe G. Hernandez



RENEWS 12/31/15

06/29/2015