

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 7/08/2014

CORNER DESIGNATION:

Z-9, Section Corner common to Sections 32 and 33 Township 6 North, Range 37 East and Sections 5 and 4, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set post for Sections 32, 33, 4 & 5 on a side hill facing the west, drove charred stake, dug pits and raised mound as per instructions."

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

S32|S33 T6N
S5|S4 R37E
2014 T5N
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap stamped as Corner common to Sections 32 and 33 Township 6 North, Range 37 East and Sections 5 and 4, Township 5 North, Range 37E from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N351°W, 64.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N17.5°E, 16.31 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S69°E, 20.20 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S11.5°W, 16.80 feet.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 840224.21
E = 8785743.98

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Mark F Wendover
Felipe G. Hernandez



RENEWS 12/31/15

06/29/2015