

USDA-FOREST SERVICE

Index

File No. A-21

T6S

R30E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

T59R30E

S35

S2 S1

T69R30E

CC

1976

OPLS 598

1

1 Describe corner monument found

1 Steel pipe extending 10" above ground with 2 1/2" brass cap stamped as shown in the diagram. Monument is in stone mound.

1

1

1

1

x

Photo Identification Data

Photo No. 1487-58

filed at Pendleton, OR

Object Ident. bearing trees

Ident. by D. Haddock

Signature

1 Describe bearing trees or other official accessories found

1 The remains of a Ponderosa Pine stump bear N26°W, 15.2' with visible scribing.

1 A 36" Ponderosa Pine snag bears S24°W, 31.7' scribed R30E S2 CC BT.

1 A 32" Douglas Fir stump bears S20°E, 45.5' scribed T6S CC BT.

1 A 10" Douglas Fir bears S59°E, 45.5' with healed scribe.

1 A 18" Douglas Fir bears S53°W, 56.5' with healed scribe.

x

Plane Coordinate Position Data

State

Zone

X

Y

Estab. by

Agency

1

1 Describe corner location relative to near-by features, also how to reach corner

1 From the junction of roads 5312 and 5320, follow 5320 east 1.6 miles to road

1 5320110. Then follow road 5320110 east 1.4 miles and follow a logging spur road

1 south through an open area to a east-west fence. Follow this fence east

1 approximately 500' to the corner.

1

x

Signature

David L. Haddock

Title

Land Surveyor

Division

Headquarters

Pendleton, OR

Date

June 1988

7100.52

CORNER RECORD (PERPETUATION)

X _____ X

Monument: Describe new monument set, or work done to preserve existing monument

Set 30" aluminum pipe 22" in the ground at the intersection of the First Standard Parallel and the section line from the south. Stamped the 2 1/2" aluminum cap as shown to the right. Made a stone mound around the monument. The new monument is about 3.49' south of the monument by OPLS 598. Set a steel fence post 5' west of the monument and attached Forest Service Land Survey Monument and Property Boundary signs. Stamped the brass cap by OPLS 598 "AM".

T5SR30E
935
 82 | 51
 T6S | R30 E
 CC
 1988
 PLS 852

x _____ x

Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Repainted red bands around trees. Attached Forest Service Land Survey Monument and Bearing Tree signs to the trees. Used old bearing trees as bearing trees for the new monument. These trees are located with respect to the new monument as follows:

The 10" Douglas Fir bears S62°30'E, 44.2'.

The 20" Douglas Fir bears S57°15'W, 51.0'.

x _____ x

Work done by David L. Haddock Title Land Surveyor Date Nov 1988
 Certified cor. record prepared? yes x no Filed at Pendleton, OR

State Registration No. 852
 or Agency
 Date Dec 1988
 Jan 1989

x _____ x

REMARKS

x _____ x

Index File No. A-21 T.6S. R.30E. M. Willamette Tract or Survey No Cor.

Index File No. A-21

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. A-21
CC


T 65 R. 30E

R.D. UKIAH County UMATILLA

Merid. _____

N.F. UMATILLA State OR

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

REMAINS OF 10" PINE STUMP BRS N26°W 153 FT MKS VISIBLE
A 36" PINE SNAG BRS S24°W 912 FT MKD R30E S2CCBT
A 32" FIR STUMP " S20°E 455 " " T65 CCBT

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

COR IS 5 FT SO. OF E-W FENCE

Signature

R.D. Begett

Title

LANDSURVEYOR

Division

Headquarters

Date

9-30-76

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

SET 2 1/2" x 30" IRON PIPE W/ BRASS CAP MKD

T55 R30E

S85

SZ | S1

T6S | R30E

1976

DPL5598

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

NEW BT'S

A 10" FIR BR S59°E 455 FT MKD T6S R30E S1 CC BT.

A 18" FIR " S53°W 565 " " T6S R30E SZ CC BT.

10

Work Done By: R. D. BAGETT Title LAND SURVEYOR Date 9-30-76 State Registration No. DPL5598
or AgencyCertified Cor. Record Prepared? Yes No Filed At: UMATILLA C.S. Date _____

11

REMARKS

Index-File No.

A-21

T.

R.

M.

Tract or Surv. No.

Cor.

12

13