

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. A-24


History of original corner establishment:

The original corner was established by Oregon PLS 933 under a Forest Service contract in June of 1977. His record reads:

Set 2 1/2" x 30" iron pipe 22" in ground with brass cap marked as shown:
From which I scribed Bearing Trees.

A 12" pine bears N. 76°47' W. 18.6 ft. mkd. E. 1/16 CC S.1 BT.
A 9" pine bears S. 07°33' W. 19.5 ft. mkd. E. 1/16 CC S.1 BT.

Nailed a brass washer mkd. PLS 933 to the BT blaze on both trees. Set a steel fence post 3 ft. East of corner. Raised mound of stone to 2" of top of pipe. Used transit and steel tape, measuring to the center of BTs.



Description of corner evidence found:

Found an iron pipe extending 4" above the ground in a mound of stone with a 2 1/2" brass cap stamped as shown to the right. A 14" White Fir bears N76°47'E, 18.6' with healed scribe. A 9" Lodgepole Pine bears S7°33'W, 19.5' scribed E1/16 S1 BT and is dead and down.


1977

E 1/16
S1
T6S R30E
PLS 933

Description of monument and accessories I established to perpetuate the original location of this corner:

I established a new bearing tree. This tree is a 9" Lodgepole Pine which bears S40°30'E, 34.9' and is scribed E1/16 S1 BT. Nailed an aluminum washer stamped RLS 852 between the letters B and T on the tree. Made bands around all three trees and painted the bands and the blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to each tree.

I certify the above corner points were perpetuated and established as hereon described on November 3, 1988.



Office of Survey Dept. County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 18th day of January, 1989
David H. Kauffman by Patricia K. Kinsberry
(COUNTY OFFICIAL) (DEPUTY)

A-24

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 1-8-89
Rec'd By KA
No. 88-13-B