


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

11-0

**History of original corner establishment:**

None



**Description of corner evidence found:**

None

**Description of monument and accessories established to perpetuate the original location of this corner**

Set 32" X 2" flanged iron pipe with brass cap marked:  
From Which

T5S R29E  
¼ S6  
T6S R30E  
1979  
PLS 346

Ponderosa Pine, 8" Dia., BRS. S39°E., 69.2 Ft. Dist.  
Marked: ¼ S6 BT

Ponderosa Pine, 16" Dia., BRS. S21½°W., 79.8 Ft. Dist.  
Marked: ¼ S6 BT

6' Iron Fence Post with "Survey Monument" sign within 5' of corner.

All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped:  
PLS 346; nailed to lower blaze.

Office of County Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the ..... day of .....

..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

A-3

**RECEIVED BY**

Form R6-7100-57 (9/71) Umatilla County Surveyor  
 Date 10-17-79  
 Rec'd By MSJ  
 No. Q-1171-B

