


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Meldrum & Campbell under General Land Office Contract No. 380.



Surveyor General Record States:

Set post for ¼ cor. From which:

- A 10" Fir bears S 57 E, 48 lks.
- A 10" Fir bears S 87 W, 11 lks.

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original SW BT as follows:

- A 20" Fir bears S87W, 7.3 ft., opened tree and found BT scribe.

Description of monument and accessories established to perpetuate the original location of this corner

At corner point, I set 2½"x30" iron pipe with brass cap marked as shown, 28" in ground, from which:

New BTs

- A 10" Fir bears N87W, 18.9 ft. marked ¼S1 T6S R29E BT.
- A 12" Pine bears N29E, 66.1 ft. marked ¼S6 T6S R30E BT.

Nailed brass washer to BT blaze.


Set steel fence posts 5+ ft. North and 5+ ft. East of corner.

Used steel tape and magnetic compass with 20° E declination.

Measured from face of blaze on original BT and center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I. Griffith
OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of Aug., 1974.
Ralph Thompson by _____
(COUNTY OFFICIAL) (DEPUTY)

C-1