


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Frank W. Campbell, under Contract No. 380

Surveyor General Record States:

40.00 set a basalt stone 10x10x10 in a mound of stone for 1/2 sec. cor.

Pine 24" in diam. brs. N. 25° E. 7 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Fd. basalt stone 10"x8"x7" dimly marked 4, loosely set in a mound of stone. from which the ORIGINAL BEARING TREE:

A 26" Pine bears N. 25° E. 4.6 ft. mkd. 1/2 in blaze that has been opened years ago.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the corner point: Set a 2 1/2"x30" iron pipe 16" in the ground with brass cap mkd as shown: From which I scribe one NEW BEARING TREE:

A 16" pine bears N. 61° W. 41.1 ft. mkd. T6S R30E 1/2 S2 BT.


I nailed a brass washed marked "OPLS 598" to the BT blaze of the tree. Set steel fence post 5 ft. south of corner. Buried original corner stone East and alongside pipe. Raised a mound of stone, 3 ft. base to within 5" of top of pipe. Corner is 30 ft. South of logging road. Used compass with 20° east variation, measuring to the center of the new BT.

REGISTERED PROFESSIONAL LAND SURVEYOR

Robert D. Bagett

OREGON JULY 12, 1963 ROBERT D. BAGETT 598

Sept. 30, 1976



Office of..... County Surveyor..... County of..... Umatilla
Oregon
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

C-21

S-60-M