

USDA-FOREST SERVICE

Index File No. C-23

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 6S. R. 30E. R.D. Ukiah County Umatilla

Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM

T. 6S., R. 30E.
C 1/4 S.1



DESCRIBE CORNER MONUMENT FOUND

None
Set brass cap

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the intersection of Oregon Highway and Five Mile Creek, go up Five Mile Creek Road about 5.0 Miles, then West by Northwest about 0.8 miles and corner is South 30 ft.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
Daniel H. Kuler

Title _____ Division OPLS Headquarters 933 Date 7-77 7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T. 6S., R. 30E.

Set 2½" x 30" iron pipe with brass cap.

C ¼ S.1

Pipe is 20" in ground.

1977

Mound of stone to cap.

PLS 933

Stamped:

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 11" pine bears N. 27°29' E. 21.7 ft.

A 12" pine bears S. 39°31' E. 22.9 ft.

Set steel fence post 2 ft. West of corner w/sign.

Painted red band around BT trees w/sign.

10

Work Done By Terry Hamby Title Party Chief Date 6/23/77 State Registration No. _____
or Agency _____Certified Cor. Record Prepared ? Yes No _____ Filed At: _____ Date _____ 11

REMARKS

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13