


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**History of original corner establishment:**

Frank W. Campbell under Contract No. 380 dated March 19, 1881:  
Set Pine Post from which

- Pine, 30" Dia., BRS. S72°E., 22 Lks. Dist.
- Pine, 30" Dia., BRS. S60°W., 63 Lks. Dist.
- Pine, 30" Dia., BRS. N68°E., 72 Lks. Dist.
- Pine, 18" Dia., BRS. N66°W., 69 Lks. Dist.



**Description of corner evidence found:**

Found no original evidence.

**Description of monument and accessories established to perpetuate the original location of this corner**

Set 32" X 2" flanged iron pipe with brass cap marked:  
From which

- Ponderosa Pine, 7" Dia., BRS. N46°E., 18.5 Ft. Dist.  
Marked: T6S R30E S5 BT
- Douglas Fir, 10" Dia., BRS. S37°E., 26.7 Ft. Dist.  
Marked: T6S R30E S8 BT
- Douglas Fir, 14" Dia., BRS. S17°W., 33.7 Ft. Dist.  
Marked: T6S R30E S7 BT
- Douglas Fir, 18" Dia., BRS. N48°W., 48.4 Ft. Dist.  
Marked: T6S R30E S6 BT

T6S R30E  
S6|S5  
S7|S8  
1979  
PLS 346

6' iron fence post with "Survey Monument" sign within 5' of corner.

All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped:  
PLS 346; nailed to lower blaze.

Office of County Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the        day of       .  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
MAY 6, 1955  
WAYNE O. HARRIS  
346

**RECEIVED BY**

**Umatilla County Surveyor**

Date 10-17-79

Rec'd By [Signature]

No. Q-1171-B

Form R6-7100-57 (9/71)