


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Meldrum & Campbell under General Land Office Contract No. 380.

Surveyor General Record States:

Set post for  $\frac{1}{4}$  cor. From which:

- A 20" Pine bears N 79 W, 56 lks.
- A 28" Pine bears East, 23 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found small mound of stone, from which:

Original BTs

- A 24" Pine snag bears N71W, 37.0 ft., scribes visible.
- A 10" Pine, dead and down, bears East, 15.2 ft., scribes visible.


Description of monument and accessories established to perpetuate the original location of this corner

At corner point, I set  $2\frac{1}{2}$ "x30" iron pipe, with brass cap marked as shown, 24" in ground from which:

New BTs

- A 12" Fir bears N43E, 22.0 ft. marked  $\frac{1}{4}$ S18 T6S R30E BT.
- A 10" Pine bears S72W, 58.5 ft. marked  $\frac{1}{4}$ S13 T6S R29E BT.

Nailed brass washer to BT blaze.  
 Set steel fence post 5+ ft. East and 5+ ft. North.  
 Used steel tape and magnetic compass with 20° E declination.  
 Measured to face of blaze on original BTs and center of new BTs.



Office of Surveyor County of Wasatch  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 13 day of August, 1977, at        o'clock        m., (signed)  
Ralph Thompson by         
 (COUNTY OFFICIAL) (DEPUTY)