


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



A PINE POST.

36" PINE S19W 121 LKS.  
40" PINE N15E 98 LKS.

Description of corner evidence found:

30" PINE S19W 89.9' SCRIBING VISIBLE  
40" PINE STUMP N15E 67.8' POSSIBLE REVERSE SCRIBING ON BARK NEAR STUMP,  
STUMP FITS FOR BEARING AND DISTANCE.

Description of monument and accessories | established to perpetuate the original location of this corner:

SET A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED: T6S R30E  
1/4 S14  
S23  
1978  
PLS 346  
MONUMENT IS SET IN A MOUND OF STONES.

16" PINE N34E 15.0' MARKED: 1/4 S14 BT

THE STUMP HAS A BEARING TREE TAG. THE OTHER BT'S HAVE A RED-PAINTED STRIPE, A BEARING TREE SIGN, AND AN ATTENTION SIGN. THE NEW TREE HAS A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE.



Office of...COUNTY...SURVEYOR..... County of...UMATILLA.....  
State of...OREGON..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19... RECEIVED SEP 11 1978  
*Wayne O. Harris* by.....  
(COUNTY OFFICIAL) (DEPUTY)