


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



A 15"x15"x10" BASALT STONE IN A MOUND OF STONES

30" PINE N60W 82 LKS.  
30" PINE S29W 125 LKS.

Description of corner evidence found:

30" DOWN PINE SNAG S29W 54.1' SCRIBING VISIBLE  
STUMP HOLE WITH PIECES OF ROTTEN STUMP N60W 82.5'

Description of monument and accessories | established to perpetuate the  
original location of this corner:

SET A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED :	T6S R30E
	S14 S13
	S23 S24
	1978
	PLS 346

MONUMENT IS IN A MOUND OF STONES.

12" PINE S54W 29.6' MARKED: T6S R30E S23 BT  
 16" PINE N23W 64.0' MARKED: T6S R30E S14 BT  
 14" PINE S34E 94.0' MARKED: T6S R30E S24 BT  
 16" PINE N29E 27.0' MARKED: T6S R30E S13 BT

ALL BT'S HAVE A RED-PAINTED STRIPE, BEARING TREE SIGNS, AND AN ATTENTION SIGN.  
THE NEW BT'S HAVE A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER  
BLAZE. THERE IS A STEEL FENCE POST NEAR THE CORNER.



Office of.....COUNTY SURVEYOR..... County of.....UMATILLA.....  
 State of OREGON....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
*Wayne O. Harris* by.....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED SEP 11 1978

N-21  
☆ GPO 799-508