


Z-1

History of original corner establishment:

ESTABLISHED ON MAY 27, 1881, BY HENRY MELDRUM

Set a basalt stone 18" x 14" x 6" in a mound of stone, from which:

A pine, 36 inches in diameter, bears S. 38° E., 172 links.



Description of corner evidence found:

Found an unmarked stone, 18" x 14" x 8", solidly set in a mound of stones which is 4 1/2 ft. at base and one foot high. The original bearing tree is now a burnt rootwad with the burnt remains of a pine log lying alongside. No marks or other evidence remains indicating this is a bearing tree. The center of this is rootwad, bears S. 38° E., 114.2 ft. from the cornerstone. Records on file at USFS offices in Pendleton and Dale Ranger Station indicate this BT was found in 1969 by J. L. Wolford, Sr. He found the BT burnt down with an old FS tag. He also found the cornerstone. In my attempt to contact Mr. Wolford, I learned he has since passed away. In order to accept this stone as the true corner point, I chained East, West, and South and found the topography calls of record to fit reasonably well, being no more than 15 ft. different than my measurements.

Description of monument and accessories established to perpetuate the original location of this corner:

Moving the cornerstone aside, I set in its place a 2" x 30" galvanized iron pipe 15" into the ground. A 2 1/2" brass cap attached is marked:

R.30E. R.31E.

I place the cornerstone alongside the iron pipe and build a mound of earth and stone around the pipe to the brass cap, from which:

T.6S. S36 | S31
T.7S. S1 | S6

PLS 1636
1981

- A 17" Ponderosa pine bears N. 41° 30' E., 110.5 ft. scribed "T.6S., R.31E., S.31, BT" on double blazes.
- A 19" Ponderosa pine bears N. 25° 30' W., 106.3 ft. scribed "T.6S., R.30E., S.36, BT" on double blazes.
- A 15" Ponderosa pine bears S. 73° 30' E., 100.5 ft. scribed "T.7S., R.31E., S.6, BT" on double blazes.
- A 9" Juniper bears S. 63° W., 34.0 ft. scribed "T.7S., R.30E., S.1, BT" on double blazes.

I placed a BT sign above the blazes and a warning sign on the back of each new BT.

I hereby certify the above corner location was perpetuated as hereon described on May 27, 1981. Witness: Dwight Bartleson De: 2008

Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon.....

I hereby certify that the within instrument was filed in this office for record on the..... day of..... June....., 1981.

David H. K...
(COUNTY OFFICIAL)

(DEPUTY)



RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd By BLS
 No. S-111-M