


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



A PINE POST

40" PINE N08E 66 LKS.
14" PINE S17W 15 LKS.

Description of corner evidence found:

40" PINE STUMP N08E 43.6' SCRIBING PARTIALLY VISIBLE
26" PINE S17W 9.9' SCRIBING VISIBLE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED:

T6S
R30E R31E
1/4
S12 S7
1978
PLS 346

THE CORNER MONUMENT IS SET IN A MOUND OF STONES.

10" PINE S86E 27.2' MARKED: 1/4 S7. BT

THE PINE STUMP HAS A BEARING TREE TAG. THE OLD AND THE NEW BT'S HAVE A RED-PAINTED STRIPE, BEARING TREE SIGNS, AND AN ATTENTION SIGN. THE NEW BT HAS A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE. THERE IS A STEEL FENCE POST ON LINE NEAR THE CORNER.



Office of..... COUNTY SURVEYOR..... County of..... UMATILLA.....
State of..... OREGON....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
Wayne O. Harris..... by.....
(COUNTY OFFICIAL)..... (DEPUTY).....

RECEIVED SEP 11 1978