

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:	Index: X-1
Quarter cor., T6S; Sec 36 of R31E & Sec 31 of R32E, WM	
Corner originally set by Rufus Moore under	1 DIAGRAM 1
Contract No. 382 dated 1881.	1 BLM brass cap 1
A retracement survey was made by the BLM under	1 1
assignment instructions dated 1967.	1 T6S 1
They found no evidence of the original corner. By	1 R31E R32E 1
proportion, they set a standard BLM monument marked as	1 1/4 1
shown, 10" in the ground in a mound of stone	1 S36 S31 1
from which a 10" Juniper bears N30°E, 151 lks. marked	1 1968 1
1/4 S31 BT, a 8" Juniper bears S44°W, 100 lks. marked	1 1
1/4 S32 BT.	1 1
In 1991 PLS1341 marked a stone which bears S75°E,	
57.96' with an X and 1/4 36 31; and drove a 1"x24"	
pipe 18" into the ground at S0°E, 4.0'.	


Description of corner evidence found:
 Found the corner monument as described from which:
 A 15" dbh Juniper bears N26°E, 124.1' with X scribed on face.
 A dead 15" dbh Juniper bears S52°W, 47.7' with X scribed on face.
 A 1" pipe bears S0 3/4°E, 4.0'.
 A rock outcrop bears S65°E, 58.0' with chiseled X and 1/4 36|31.

Description of monument and accessories I established to perpetuate the original location of this corner:
 Cleared brush and debris from corner and set new bearing trees as follows:
 A 10" dbh Juniper bears S35 3/4°W, 49.3' scribed 1/4 S36 BT.
 The bearings are true based on the GPS bearings to the surveyed steel post which bears S0 1/4°W at 19.1'.
 An aluminum washer stamped RLS 852 is nailed between the letters B and T. on the new tree. All the BT's have LSM and BT signs attached.
 Painted 6" red bands around all the trees and painted the scribe blazes red.

This work was done May 24, 1994.



David L. Haddock



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-94
 Rec'd By RR
 No. 94-97-R