


2-17

History of original corner establishment:

Original Survey by Meldrum and Campbell, Contract No. 380, 1881, Set a Pine post for 1/4 Sec. Cor.

Pine 6 in. dia. bears N64°W 50 lks.

Fir 26" dia. bears S32°E 32 lks.




Description of corner evidence found:

No trace of the orig. corner post remains. Found a 2 1/2" Galvanized Iron Pipe extending 8" above ground, with brass cap attached, marked:

From Which: an original 6" Pine, now a 7" P. Pine snag, with scribing "BT" visible on a previously opened blaze, bears N66°W 33.0 feet, and an orig. 26" Fir, now a 27" Douglas Fir snag, partially opened, scars visible, bears S38 1/2°E 21.1 feet. And BT's apparently established by the BLM: A 14" Douglas Fir with scribing "1/4 S35 BT" visible on an unhealed single blaze, bears N 5 1/2°W 11.3 feet; And a 14" Douglas Fir with scribing "1/4 S 2 BT" visible on a single blaze bears S56°E 42.0 feet.

U.S. Dept. of the Interior
Bureau of Land Management



Description of monument and accessories I established to perpetuate the original location of this corner:

Corner located on wooded north slope, 18 feet north of an E-W fence.

Staff Compass and Steel Tape

Declination 19° East

July 27, 1982

Witnesses: Gary Langlitz
Greg Orton
Jeff Anderson



Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 18 day of January, 1983
David H. Kline by _____
(COUNTY OFFICIAL) (DEPUTY)

2-17

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 03-03 B