


11-1

**History of original corner establishment:**

Corner position established by the Bureau of Land Management during survey performed between 1967 and 1980:

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 15 ins. in ground to bedrock and in a mound of stone 3 ft. base to top, with brass cap mkd.

Raise mound of stone 3 ft. base 2 ft. high S of corner. 1/4 S6  
T6S R32E  
1968



**Description of corner evidence found:**

Found a 2 1/2" diameter iron pipe with brass cap marked: U.S. Dept. of Interior  
Bureau of Land Management  
Firmly set in a mound of stone as described in the BLM record.

1/4 S6  
T6S R32E  
1968

**Description of monument and accessories established to perpetuate the original location of this corner:**

We establish the following bearing objects:

A 5/8"x30" iron rod driven 18" in the ground and supported in a mound of stone, 3 ft. dia. at the base to top of rod, with plastic cap marked "AP & A", bears S45°W 15.0 feet.

And a 5/8"x30" iron rod driven 15" in the ground and supported in a mound of stone, 3 ft. diameter base to top of rod, with plastic cap marked "AP & A" bears S59°E 15.5 feet.

Corner is located 2 ft. north of an E-W fence.

Magnetic Compass (20° East Declination)  
Steel Tape

September 6, 1984

Witnesses:

Gary Langlitz, LS 1099  
Ray Crapo  
Greg Orton



Office of Surveyor County of Umatilla  
State of Oregon I hereby certify that the within instrument was filed in this office  
for record on the 06 day of October, 1984  
David Lumbkin by Betty Cochran  
(COUNTY OFFICIAL) (DEPUTY)