

Index
File No. A-9

CORNER RECORD (SEARCH)

(Ref. FSM 7.151.4)

Tract or Survey No. _____ Cor. No. _____


T GS R. 32E

R.D. UKIAH County UMATILLA

Merid. WILLAMETTE

N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND
Found a 2½" iron pipe, firmly set, with brass cap marked as described in Gaylord Record (refer to Umatilla Co. Surveyor's Record No. 82-102-R), from which:

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
The stumps of the original Campbell BT's exist as described in the Gaylord Record, and BT's marked by Gaylord,
A 10" Douglas Fir bears S 13°E 73.9 ft. This tree is alive and and in good condition, it does not appear to have been marked as described in the Gaylord Record.
And a 16" Douglas Fir, alive with partially healed blaze bears S 40°W 90.4 links.

PHOTO IDENTIFICATION DATA

Photo No. 280-293
Filed At. UMATILLA NAT. FOR.
Object Ident. DIRECT
Ident. By S. Jangley
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature

Title

Division

Headquarters

Date

LS 1099

Date _____
FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

None

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

We scribe the SE Gaylord BT as follows, scribed "CC T6S R32E S4 BT" on a double blaze, attached a brass washer marked "LS 1099" to lower blaze.

Work Done By Gary Langlitz Title LS 1099 Date 8-84 State Registration No. or Agency

Certified Cor. Record Prepared? Yes No Filed At UMATILLA Co. Surveyor Date 9-84

REMARKS

Index File No. A-9 T. 6S R. 32E M. WILLAMETTE Tract or Surv. No.

Cor.