


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Frank W. Campbell under G.L.O. contract number 468, dated April 12, 1883 set a sandstone 20"X 13"X 6" from which:



- A Pine, 30" dia., N19°E, 26 lks.
- A Pine, 18" dia., S66°E, 8 lks.
- A Pine, 20" dia., S10°W, 8 lks.
- A Pine, 30" dia., N57°W, 25 lks.

U.S. Cadastral Surveyors under special instructions Group Numbers 350 and 643 found the original sandstone 25"X 16"X 15" from which:

- A Pine stump, 14" dia., N19°E, 26 lks., with fragmentary scribing.
 - A Pine stump, 20" dia., S3½°W, 8 lks., with scribing visible.
- (Continued on Page 2 of 2.)

Description of corner evidence found:

I found a 2½" iron pipe with a brass cap marked: in a mound of stone, from which:

T6S R32E
S22 | S23
S27 | S26
1967

- Pine stump, approx. 14" dia., N19°E, 17.2 ft. with scribing visible.
- Pine stump, approx. 20" dia., S3½°W, 5.3 ft.
- Root hole, N51½°W, 16.5 ft., with a scribed BT lying on the ground to the south.
- A Ponderosa Pine, 8" dia., N35½°E, 23.8 ft., with healed blaze.
- A Ponderosa Pine, 12" dia., S75°E, 25.1 ft., with healed blaze.
- A Ponderosa Pine, 14" dia., S37½°W, 57.4 ft., with healed blaze.
- A Ponderosa Pine root collar, N51½°W, 16.5 ft., with rotted and scribed remains of BT on the ground downhill.

Description of monument and accessories established to perpetuate the original location of this corner:

I marked a new BT:

A Ponderosa Pine, 13" dia., N29 3/4°W, 37.1 ft., marked: T6S R32E S22 BT

BTs have blaze and a 6" band painted red, BT tags and "Attention" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 16½°E.

Nov. 1, 1986



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 12-1-86
Rec'd By RA
No. 86-136-M

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

(Continued from Page 1 of 2.)

A root hole, N51 1/2°W, 25 lks., with a 20" dia. pine down alongside with scribing visible.

At the corner point they set a 2 1/2" X 28" iron post with a brass cap marked:
from which:

A Pine, 5" dia., N35 3/4°E, 36 lks.

A Pine, 7" dia., S75°E, 38 lks.

A Pine, 10" dia., S37 1/2°W, 87 lks.


A Pine, 6" dia., N51 1/2°W, 48 lks.

T68 R32E

S22 | S23

S27 | S26

1968



They deposited the original stone alongside the iron post.

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

GPO-799-276

Date _____

Rec'd By _____

No. 86-136-M