


History of original corner establishment:

Frank W. Campbell under G.L.O. contract number 468, dated April 12, 1883, set a pine post 4 ft. long and 4" square 24" in the ground from which:

- A Pine, 30" dia., S80°W, 30 lks.
- A Pine, 20" dia., S19°E, 71 lks.
- A Pine, 10" dia., N41°E, 49 lks.
- A Pine, 10" dia., N54°W, 56 lks.



U.S. Cadastral Surveyors under special instructions Group Numbers 350 and 643 set corner at record distance from original BTs:

- A Pine, 16" dia., N41°E, 49 lks.
- A Pine, 13" dia., S19°E, 71 lks.

(Continued on Page 2 of 2.)

Description of corner evidence found:

I found a 2½" iron pipe with a brass cap marked from which:

T6S R32E  
S23|S24  
S26|S25  
1967

- A Ponderosa Pine, 21" dia., N41°E, 32.3 ft. with scribing visible.
- A Ponderosa Pine, 17" dia., S21°E, 46.9 ft., with scribing visible.
- A burned pine stump, approx. 3 ft. dia., S20°W, 19.8 ft., with scribing visible.
- A Ponderosa Pine, 28" dia., N54°W, 37.0 ft., with a healed blaze.
- A Douglas Fir, 10" dia., N34°E, 40.9 ft., with a healed blaze.
- A Douglas Fir, 21" dia., S42°E, 26.4 ft., with a healed blaze.
- A Douglas Fir, 12" dia., S17°W, 33.7 ft., with a healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

I built a small mound of stone around the monument. I painted the blaze of the BTs and a 6" band around them red and attached new BT tags and "Attention" signs. I drove a 6' steel fence post within 5' of the corner and attached an "Attention" sign.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18½°E.

Oct. 31, 1986



Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 12-11-86  
 Rec'd By KA  
 No. 86-139-M

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

(Continued from Page 1 of 2.)  
A Pine, 28" dia., South, 30 lks.  
A Pine, 25" dia., N54°W, 56 lks.

At the corner point they set a  
2 1/2" X 28" iron post with a brass cap  
marked:  
from which:

T68 R32E  
S23 | S24  
S26 | S25  
1967



A Fir, 7" dia., N34°E, 62 lks.  
A Fir, 15" dia., S42°E, 40 lks.  
A Fir, 5" dia., S12°W, 51 lks.

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:



Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 86-139-M