

USDA-FOREST SERVICE

Index

File No. S-14

T65 R32E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

1 Describe corner monument found
 1 Standard BLM brass cap stamped as shown in the corner diagram in a mound
 1 of stone.

1
 NW-- 527
 161
 1968

x

Photo Identification Data

1 Describe bearing trees or other official accessories found

Photo No.

1 A 15" Ponderosa Pine bears N80 E, 40.6'.

filed at

1 A 19" Ponderosa Pine bears N20 W, 16.5'.

Object Ident.

1

Ident. by

1

Signature

1

x

Plane Coordinate Position Data

1 Describe corner location relative to near-by features, also how to reach corner

State

Zone

1 From the junction of roads 55 and 5506, follow road 55 0.3 miles east to road

X

1 070. Follow this road 0.2 miles north to road 073. Follow this road north 0.7

Y

1 miles to the end of the road. Go south 1200' to the corner which is about 25'
 1 west of a small stream channel.

Estab. by

1

Agency

x

Signature

Title

Division

Headquarters

Date

7100.52

David L. Haddock

Land Surveyor

Pendleton, OR

July 1988

CORNER RECORD (PERPETUATION)

X _____ X
Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' east of the monument and attached Forest Service Land Survey Monument and Property Boundary signs. Cleared down tree off monument.

X _____ X
Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Made bands around trees and painted bands and scribe blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to the trees.

X _____ X
Work done by David L. Haddock Title Land Surveyor Date July 1988 State Registration No. 852
Certified cor. record prepared? yes no x Filed at or Agency Date

X _____ X
REMARKS

X _____ X