

USDA-FOREST SERVICE

Index

File No. T-13

T6S

R32E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

114

x S281S27

x T6S R26E

1967

1 Describe corner monument found

1 Standard BLM brass cap stamped as shown in the corner diagram in a mound of stone.

1

1

1

1

x

Photo Identification Data

Photo No.

filed at

Object Ident.

Ident. by

Signature

1 Describe bearing trees or other official accessories found

1 A 33" Ponderosa Pine bears S30 E, 15.7'.

1 A 14" Ponderosa Pine bears N12 E, 43.1'.

1 A burned Ponderosa Pine stump bears N56 W, 55.7'.

1 A 17" Ponderosa Pine bears S64 W, 62.8'.

1

x

Plane Coordinate Position Data

State

Zone

x

y

Estab. by

Agency

1 Describe corner location relative to near-by features, also how to reach corner

1 From the junction of roads 55 and 5506, follow road 55 0.5 miles west to road

1 063. Follow this road 0.1 miles north to the 1/4 corner which is about 50' east

1

1

1

x

Signature

Title

Division

Headquarters

Date

7100.52

David L. Haddock

Land Surveyor

Pendleton, OR

July 1988

CORNER RECORD (PERPETUATION)

X-----X  
Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' south of the monument and attached Forest Service Land Survey Monument and Property Boundary signs.

X-----X  
Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Made bands around trees and painted bands and scribe blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to the trees. Did the same to the stump.

X-----X  
Work done by David L. Haddock Title Land Surveyor Date July 1988 State Registration No. 852  
Certified cor. record prepared? yes no x Filed at Date

X-----X  
REMARKS

X-----X