

USDA-FOREST SERVICE

Index

File No. J-14

T65

R32E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

W1/16

C---C

S27

1979

1 Describe corner monument found
 1 Standard BLM brass cap stamped as shown in the corner diagram in a mound
 1 of stone.
 1
 1
 1
 1

x

Photo Identification Data

Photo No.

filed at

Object Ident.

Ident. by

Signature

1 Describe bearing trees or other official accessories found
 1 A 13" Ponderosa Pine bears S62 E, 41.5'.
 1 A 15" Ponderosa Pine bears S56 W, 62.6'.
 1
 1
 1

x

Plane Coordinate Position Data

State

Zone

X

Y

Estab. by

Agency

1 Describe corner location relative to near-by features, also how to reach corner
 1 From the junction of roads 55 and 5506, follow road 55 0.3 miles east to road
 1 070. Follow this road 0.1 miles north to a road not shown on the map which goes
 1 west. Follow this road west 0.1 miles to where the center one quarter corner is
 1 plainly visible about 100' south of the road. Follow the posted line west one
 1 quarter of a mile to the CW1/16 corner.
 1

x

Signature

Title

Division

Headquarters

Date

7100.52

Daniel L. Haddock Land Surveyor

Pendleton, OR

July 1988

CORNER RECORD (PERPETUATION)

X _____ X
 Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' west of the monument and attached Forest Service Land Survey Monument and Property Boundary signs.

x _____ x
 Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Made bands around trees and painted bands and scribe blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to the trees.

x _____ x	State Registration No.	
Work done by David L. Haddock Title Land Surveyor Date July 1988	or Agency	852
Certified cor. record prepared? yes no x Filed at	Date	

x _____ x
 REMARKS

x _____ x