


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

U-9

History of original corner establishment:

U.S. Cadastral Surveyors under special instructions Group Numbers 350 and 643 set a 2 1/2" X 28" iron post with a brass cap marked: in a stone mound, from which:

S 1/16
S 29 1/3 28
1968



A Pine, 6" dia., N64°E, 66 lks.
A Pine, 10" dia., N5°W, 28 lks.

Description of corner evidence found:

I found a 2 1/2" iron pipe with a brass cap marked: in a stone mound, from which:

S 1/16
S29 | S28
1968

A Ponderosa Pine, 14" dia., N5°W, 18.5 ft. with a healed blaze.

A Ponderosa Pine, 9" dia., N69°E, 42.5 ft., with a healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20°E.

Nov. 2, 1986



Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 12-11-86
Rec'd By DA
No. 86-135-M