


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-8

History of original corner establishment: BLM set corner, under US Survey Group Nos. 350 and 613 dated August 21, 1967, portion of subdivisional lines, T.6 S., R.32 E., WILLAMETTE MERIDIAN, OREGON, AND STATES: SET IRON POST, 28 ins. long, 2 1/2 ins. diam., 18 ins. in the ground, to solid rock, in a mound of stone, 3 ft. to base, to top, with brass cap mkd.



E 1/16 S 29
 S 32
 1968

FROM WHICH

A Fir, 12 ins. diam., bears S. 28° E., 56 1/2 lks. dist., mkd E 1/16 S 32 BT
A Fir, 12 ins. diam., bears N. 63° W., 37 lks. dist., mkd E 1/16 S 29 BT

Description of corner evidence found: 3/4" BLM BRASS CAP ON 2 1/2 in. iron post, in mound of stone,

MKD. E 1/16 S 29
 S 32
 1968

FROM WHICH

a Fir, 16 ins. diam., bears S. 36° E., 37.10 Ft. dist. (record S. 28° E., 56 1/2 lks dist.) with healed blaze
USFS 54-3
a Fir, 16 ins. diam., bears N. 38° W., 24.50 Ft. dist. (record N. 63° W., 37 lks dist.) with healed blaze
USFS 54-3 sign attached

Description of monument and accessories I established to perpetuate the original location of this corner: Set a steel guard post with USFS 54-2 and 54-9 signs attached 5-ft. S. of corner. ATTACHED USFS 54-9 signs to and painted 6 ins. red band around BT's.

MAGNETIC DECLINATION USED AT THIS CORNER TO EST. BEARINGS: DE. 19° E

Witness: Ken Bates
 Scott Keike

I HEREBY CERTIFY THE ABOVE CORNER POINT WAS PERPETUATED IN AUGUST 1990 AS HEREON STATED.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Guy W. Streamer
OREGON
SEPTEMBER 23, 1977
GUY W. STREAMER, JR.
1341

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....
David H. Klien by.....
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 3-91
Rec'd By KA
No. 91-22-R