

USDA-FOREST SERVICE

Index

File No. W-21

T6S

R32E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County

State

Cor.

No.

Umatilla

Oregon

x ----- 1 ----- 1

Corner Diagram

1
N--
16
S351S36

1 Describe corner monument found
1 Standard BLM brass cap stamped as shown in the corner diagram.

x ----- 1 ----- x

Photo Identification Data

Photo No.

filed at

Object Ident.

Ident. by

Signature

1 Describe bearing trees or other official accessories found
1 A 12" Ponderosa Pine bears S86 E, 27.7'.
1 A 12" Douglas Fir bears S10 W, 14.5'.

x ----- 1 ----- x

Plane Coordinate Position Data

State

Zone

X

Y

Estab. by

Agency

1 Describe corner location relative to near-by features, also how to reach corner
1 From the junction of roads 55 and 5507, follow road 5507 southeast 1.7 mile
1 to road 175. Follow road 175 about 200 feet. The corner is located in a swampy
1 area about 300' south of the road.

x ----- 1 ----- x

Signature

Title

Division

Headquarters

Date

7100.52

David L. Hasdlock
Land Surveyor

Pendleton, OR

July 1988

CORNER RECORD (PERPETUATION)

X _____ X
Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' west of the monument and attached Forest Service Land Survey Monument and Property Boundary signs.

X _____ X
Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Made bands around trees and painted bands and scribe blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to the trees.

X _____ X
Work done by David L. Haddock Title Land Surveyor Date July 1988 State Registration No. 852
Certified cor. record prepared? yes no x Filed at Date

X _____ X
REMARKS

X _____ X