


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

W-6

History of original corner establishment: BLM set corner during survey of subdivision of certain sections: Township 6 South, Range 32 East, of the Willamette Meridian, Oregon, under US Survey Group Numbers 350 and 643, August 1967. The record of the survey states: Set on iron post, 28 ins. long, 2 1/2 ins. diam, 14 ins. in the ground to solid rock, in a mound of stone, 3 ft. base, to top, with brass cap mko. NW 1/16 S 32, 1968 From which: A fir, 8 ins. diam, bears S. 85° E., 8 lks. dist., mko. NW 1/16 S 32 1st. A fir, 8 ins. diam, bears S. 77° W., 60 lks. dist., mko NW 1/16 S 32 1st.



Description of corner evidence found: 3/4" BLM Brass cap mko. T 6 S R 32 E NW 1/16 S 32 set on 22" iron post; in mound of stone, from which: 1968

A fir, 12 ins. diam, bears S. 78° 11' W., 39.80 ft. dist., HEALED BLAZE
A fir, 12 ins. diam, bears S. 85° 47' E., 6.40 ft. dist., HEALED BLAZE

Description of monument and accessories established to perpetuate the original location of this corner: BEARING TREE, A FIR, 12 ins. diam., bears N. 15° 22' E., 19.50 ft. dist., mko. NW 1/16 S 32 1st, with BRASS WASHER, USFS SIGNS 54-3 AND 54-9 ATTACHED, RED BAND PAINTED AROUND TREE.

Set steel guard post 5 ft. EAST OF CORNER WITH 54-2 AND 54-9 SIGNS ATTACHED
magnetic declination used at this corner to establish bearings: DE. 19° E.

Witness: Ken Bates
Scott Kriska

I HEREBY CERTIFY THE ABOVE REFERENCED CORNER WAS PERPETUATED IN OCTOBER 1990, AS HEREON STATED.

REGISTERED PROFESSIONAL LAND SURVEYOR

GUY W. STREAMER
GUY W. STREAMER, JR.
1341
SEPTEMBER 23, 1977

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
David H. Klein by.....
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Survey
Date 3-91
Rec'd By KA
No. 91-22-R