


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: BLM set corner during survey of subdivision of certain sections: Township 6S Range 32E of the Willamette Meridian, Oregon, under US Survey Group Numbers 350 and 643, August 1967. The record of the survey states: SET AN IRON POST, 28 ins. long, 2 1/2 ins diam., 24 ins. in the ground, in a mound of stone, 2 1/2 ft. base, to top, with brass cap MKO. N 1/16 S 32 FROM WHICH: A FIR, 8 ins. diam, bears S 87 1/2° E,



87 lks. dist, MKO. CN 1/16 S 32 BT. A FIR, 7 ins. diam, bears S. 56° W.,
5 lks. dist, MKO. CN 1/16 S 32 BT.

Description of corner evidence found: 3 1/4" BLM BRASS CAP MKO. N 1/16 S 32, set on 2 1/2" iron post, in mound of stone, 1968

From which:

- A 12 ins. fir, bears S 85° 45' E, 58.10 ft. dist, HEALED BLAZE
- A 10 ins. fir, bears S 57° W., 3.30 ft. dist, HEALED BLAZE

Description of monument and accessories established to perpetuate the

original location of this corner: BEARING TREE, A 10 ins. fir, bears N. 03° E, 42.40 ft. dist, MKO. CN 1/16 S 32, BT, with BRASS WASHER, USFS SIGNS 54-3 AND 54-9 ATTACHED RED BAND PAINTED AROUND TREE.

Set steel guard post with USFS 54-2 and 54-9 signs 5 ft. west of corner

Magnetic declination used at this corner to establish bearings: Dec. 19° E

Witness: Ken Bates
Scott Keaton

I HEREBY CERTIFY THE ABOVE CORNER POINT WAS PERPETUATED IN OCTOBER 1990 AS HEREON STATED

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Guy W. Streamer

OREGON
SEPTEMBER 23, 1977
GUY W. STREAMER, JR.
1341

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

David H. Klein by.....

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 3-91

Rec'd By KA

No. 91-22R