

USDA-FOREST SERVICE

Index

File No. X-21

T6S R32E

Merid. Willamette

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

R.D. North Fork John Day

N.F. Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

1 | 4
S35 | S36
T6S | R32E
1967

1 Describe corner monument found
1 Standard BLM brass cap stamped as shown in the corner diagram.

x

Photo Identification Data

Photo No. 280-243
filed at Pendleton, OR
Object Ident. Bearing Trees
Ident. by David L. Haddock
Signature

1 Describe bearing trees or other official accessories found
1 A 18" Ponderosa Pine bears N68 E, 22.4'.
1 A 20" Ponderosa Pine snag bears S51 W, 42.2'.
1 A 13" Douglas Fir bears S40 E, 56.8'.
1 A 15" Douglas Fir bears S16 W, 79.2'.

x

Plane Coordinate Position Data

State Zone

X

Y

Estab. by

Agency

1 Describe corner location relative to near-by features, also how to reach corner
1 From the junction of roads 55 and 5507, follow road 5507 southeast 1.7 mile
1 to road 175. Follow road 175 0.4 miles to a point 120' before the fence crossing
1 of the road. Follow the posted line west 800' to the corner.

x

Signature Title
David L. Haddock Land Surveyor

Division

Headquarters
Pendleton, OR

Date 7100.52
July 1988

CORNER RECORD (PERPETUATION)

X _____ X
 Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' east of the monument and attached Forest Service Land Survey Monument and Property Boundary signs.

x _____ x
 Accessories: Describe new RT's witness objects etc. established, or work done to preserve existing evidence

Made bands around trees and painted bands and scribe blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to the trees.

x _____ x							
Work done by	David L. Haddock	Title	Land Surveyor	Date	July 1988	State Registration No.	
Certified cor. record prepared?	yes		no x	Filed at		or Agency	852
						Date	

x _____ x
 REMARKS

x _____ x
 Index File No. X-21 T.6S. R.32E. M. Willamette Tract or Survey No Cor.