


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-6

History of original corner establishment: BLM set corner during survey of subdivision of certain sections: Township 6 South, Range 32 East of the Willamett Meridian, Oregon, under US Survey Group nos. 350 and 643, August, 1967. THE RECORD OF THE SURVEY STATES: Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, in a mound of stone, 2 1/2 ft. base, to top, with brass cap mko. $c \frac{W 1/16}{S 32} c$ FROM WHICH: A Fir, 12 ins. diam., bears N. 24° E., 8 1/2 lks. dist., mko. CW 1/16 S 32 BT. A Fir, 10 ins. diam., bears S. 77° W., 36 lks. dist. mko CW 1/16 S 32 BT.



Description of corner evidence found: 3 1/4" BLM BRASS CAP MKO: $c \frac{W 1/16}{S 32} c$ set on 2 1/2" iron post, in a mound of stone, From which:

- A Fir, 16 ins. diam., bears S. 78° 40' W., 23.60 ft. dist., HEALED BLAZE
- A Fir, 14 ins. diam., bears N. 22° 15' E., 5.20 ft. dist., HEALED BLAZE

Description of monument and accessories I established to perpetuate the original location of this corner: BEARING TREE, A FIR, 10 ins. diam., bears S. 22° 30' E., 35.46 ft. dist., mko CW 1/16 S 32 BT, with brass washer, USFS SIGNS 54-3 AND 54-9 SIGNS ATTACHED, Red band painted around tree.

set steel guard post with USFS SIGNS 54-2 AND 54-9 ATTACHED, 5 FT NORTH

MAGNETIC DECLINATION USED TO ESTABLISH BEARINGS AT THIS CORNER: Dec. 19° E

Witness: Ken Bates
Scott Kriska

I HEREBY CERTIFY THE ABOVE CORNER POINT WAS PERPETUATED IN OCTOBER 1990, AS HEREON DESCRIBED.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Guy W. Streamer
 GUY W. STREAMER, JR.
 SEPTEMBER 23, 1977
 1941

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
David H. Kiser by.....
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 3-91
 Rec'd KA
 No. 91-22-R