

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

---

History of original corner establishment:

Quarter cor. Sec. 32 & 33 of T.6S. R.32E., W.M.  
 Corner originally set by Frank Campbell under  
 Contract No. 468 dated 1883.  
 Set a basalt stone, 15x15x4 in., 10 in. in ground,  
 for 1/4 sec. cor. marked 1/4 on West face from which:  
 A pine 6" diam., bears. S60°W, 15 lks., mkd. 1/4S BT.

Index: X-9

1	DIAGRAM	1
1	BLM brass cap	1
1		1
1	T6S R32E	1
1	1/4	1
1	S32;S33	1
1		1
1		1
1	1968	1
1		1

A dependent resurvey was made by the BLM under special instructions dated 1967. They found the original pine with scribe marks. At the corner point, they set a standard BLM monument marked as shown. They set a new bearing tree: A Fir, 16" diam., bears S87°E, 43 lks. dist., mkd. 1/4 S33 BT.

In 1991, PLS 1341 added the following witnesses: A pine, 18" diam., bears S61°50'W., 59.60' dist., mkd. 1/4 S32 BT. A pine, 16" diam., bears N69°53'W, 58.20 ft. dist., mkd. 1/4 S32 BT. A 1"x24" iron pipe 18" in the ground bears N0°W, 5 ft. dist.

Description of corner evidence found:

Found the corner monument as described from which:  
 A 20" dbh Western Larch bears S69 1/4°W, 59.6' with visible scribe.  
 A 20" dbh Western Larch bears N72°W, 58.2' with visible scribe.  
 A 20" dbh Douglas Fir bears S89 3/4°E, 28.2' with healed blaze.  
 A 1" iron pipe exposed 6" bears N0°W, 5.0'.

Description of monument and accessories I established to perpetuate the original location of this corner:

Cleared brush and debris from corner and set new bearing trees as follows:


A 19" dbh Ponderosa Pine bears N23 3/4°E, 82.6' scribed 1/4 S33 BT. The bearings are true based on the GPS bearings to the surveyed steel post which bears N0°07'E, 49.3'.

An aluminum washer stamped RLS 852 is nailed between the letters B and T. on the new tree. All the BT's have LSM and BT signs attached. Painted 6" red bands around all the trees and painted the scribe blazes red.

This work was done May 30, 1994.



*David L. Haddock*



Office of \_\_\_\_\_ County of \_\_\_\_\_  
 State of \_\_\_\_\_, I hereby certify that the within instrument was filed  
 in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.

\_\_\_\_\_ by \_\_\_\_\_  
 ( COUNTY OFFICIAL ) ( DEPUTY )

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County  
 Date 7-94  
 Rec'd by KR  
 No. 94-98-R