


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-1

History of original corner establishment: Record of the orig. survey states: Set a fir post for cor. to Tps. 6&7 S., Rgs. 31&32 E. from which a, Fir 10 in. in diam. bears N. 44° E. 22 lks dist.  
 Fir 10 " " " " N. 47° W. 145 " "  
 Pine 16 " " " " S. 13° W. 13 " "  
 Pine 22 " " " " S. 60° E. 9 " "



Dated June 2, 1881 by Henry Meldrum, US Deputy Surveyor. BLM dependent resurvey of the west boundry, T.6 S.,R.32 E.,W.M. Oregon, states: From the corner of T.6&7 S.,R.31&32 E.,determined at record bearing and distance from the remaining original bearing trees: A fir, 14ins. diam.,bears N.44°E.,22 lks. dist.,with healed blaze  
 A pine,24 ins. diam.,bears S.60°E. 9 lks.dist.,with healed blaze  
 A pine,15 ins, diam.,bears S.13°W. 13 lks, dist.,with healed blaze  
 At the corner point, set an iron post, 28 ins. long, 2½ ins. diam.,24 ins. in the ground in a mound of stone, 2½ ft. base, to top, with brass cap mkd; T.6&7 S.R.31&32 E. Sec 1,6,31,3  
 From which a new bearing tree:

A fir, 12 ins. diam.,bears N.70°W.,60 lks. dist.,mkd. T 6 S R 31 E S36 BT  
**Description of corner evidence found:**  
 3½"BLM brass cap mkd. T.6&7 S. R.31&32 E. Sec 1,6,31,36 1968 , set on 2½" iron post, in a mound of stone, a basalt stone 12" X 5" with 6 notches cut on north face set along side monument (no record of stone in previous surveys)  
 From which:  
 A fir, 19 ins. diam.,bears N.85° 30' E.,14.80 ft. dist.,(N.44° E.,22 lks) with healed blaz  
 A fir, 25 ins. diam.,bears N.47° W.,145 lks. dist.,with healed blaze  
 A pine, 21 ins. diam.,bears S.13° W.,13 lks dist.,with healed blaze  
 A pine, 26 ins. diam.,bears S.54° E.,6.90 ft. dist.,(S.60° E.,9lks) with healed blaze  
 A fir, 18 ins. dist.,bears N.61° 30' W.,39.60 ft. dist..(N.70°W.,60 lks) with healed blaze

**Description of monument and accessories | established to perpetuate the original location of this corner:** Set a steel guard post 4 ft. North of monument with USFS 54-2 and 54-9 signs attached.

Magnetic declination used at this corner to est. bearings: De. 19° E.

I hereby certify the above corner point was perpetuated in Aug. 1990 and Feb. 1991 as hereon stated.

Witness: Ken Bates

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Guy W. Streamer*

OREGON  
SEPTEMBER 23, 1977  
GUY W. STREAMER, JR.  
1341

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
*Daniel H. Klein*  
 (COUNTY OFFICIAL) by..... (DEPUTY)

A-1

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 3-91  
 Rec'd By KA  
 No. 91-22-R