

C-1

C-25

History of original corner establishment:

Original Survey by Frank Campbell under Contract 468, 1883. The original corner position has been re-established from evidence of the original survey by the Bureau of Land Management in 1968, as follows:


The 1/4 sec. cor. of Sec's. 1 and 6, monumented with the original basalt stone, 16x15x8 ins., mkd. 1/4 on N. face, from which the remains of the original bearing trees:

A Ponderosa Pine, 25 ins. dia., bears N12°E 9 lks dist., with healed blaze (Record 5 lk).

A Ponderosa Pine stump, 18 ins. dia., bears S37°W 42 lks dist., with scribe marks 1/4 S BT visible on open and weathered blaze (Record S 44°W).

At the Corner Point:

Set an iron post 28 ins. long, 2 1/2 ins. dia., 20 ins. in the ground, to solid (CONTINUED ON PAGE 2)



Description of corner evidence found:

Found the 1968 BLM brass cap monument firmly set and in good condition, and original and 1968 resurvey bearing trees as previously described, except that the new BT marked in 1968 by the BLM is now a dead standing snag, approx. 10' tall, with scribing "1/4 S1 BT" visible on an unhealed single blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

We mark a new BT in Section 1 as follows:

A 14" Ponderosa Pine, scribed "1/4 S1 BT" on a double blaze bears N89°W 77.0 feet with brass washer marked "LS 1099" attached to lower blaze.

Staff Compass (Declination 20° East)
Steel Tape

Corner is located on gentle SE slope in a N-S fenceline.

August 15, 1984

Witnesses:

Gary Langlitz, LS 1099
Greg Orton

REGISTERED PROFESSIONAL LAND SURVEYOR

Gary Langlitz
ON
GARY L. LANGLITZ
1983

C-25

Office of Surveyor County of
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of October 1984
David Krumboltz by Billy Cochran
(COUNTY OFFICIAL) (DEPUTY)


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

rock, in a mound of stone 3 ft. base, to top, with brass cap marked:

from which a new bearing tree:

A Ponderosa Pine, 11 ins. dia. bears S31°W 89 lks. dist., marked 1/4 S1 BT.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

0-25

84-150-R