


T. 6 S. R. 33 E.  
Merid. Willamette

R.D. North Fork John Day  
N.F. Umatilla

County Umatilla  
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 3 1/4" aluminum cap set flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

8" Englemann Spruce Snag, S. 83 3/4 E., 21.8 feet, with burnt out double blaze.  
7" Englemann Spruce Snag, N. 2 W., 21.8 feet, with burnt out double blaze.

PHOTO IDENTIFICATION DATA

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of roads 52 and 5507 travel southeasterly on 52 approximately 0.41 miles.  
Then walk southerly approximately 200 feet to the head of an unnamed creek and the corner.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/21/1997

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 23" in the ground, S. 27 E., 25.8 feet.

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 20" in the ground, N. 66 1/2 W., 17.5 feet.

Work Done By D. Schlaich Title Land Surveyor Date 10/21/1997 State Registration No. \_\_\_\_\_  
or Agency \_\_\_\_\_

Certified Corner Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5507 travel southeasterly on 52 approx. 0.41 miles. Then walk southerly approx. 200 feet to the head of an unnamed creek and the corner.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,471,083.69'

Y: 497,551.36'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT  
5/8" by 24" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS AP-519 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE  
8" Englemann Spruce, N. 2° E., 21.8 ft., mkd. "WB/519" "BT" on double blaze.  
8" Englemann Spruce, S. 83° E., 21.6 ft., mkd. "WB/519" "BT" on double blaze.  
Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

33 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-519