


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established



Description of corner evidence found:

None

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Description of monument and accessories established to perpetuate the original location of this corner

North Fork John Day Wilderness, North Fork John Day Unit, Point Number 473

This point is located in the NE 1/4 of section 36, T. 6 S., R. 33 E.

At a point 200 feet southeasterly of and perpendicular to the centerline of Road 5507 and on a spur ridge as described in the wilderness boundary description. Set a 2 1/2" X 30" flared aluminum pipe 24" into the ground with a 3" aluminum cap marked as shown in the diagram above. From which:

A 12" white fir bears S 36° 30' W, 16.5 feet, scribed "WB/473 BT" on a single blaze.

An 11" Western Larch bears N 73° E, 23.2 feet, scribed "WB/473 BT" on a single blaze. A 27-6a, "National Forest Wilderness", sign is posted on this bearing tree.

A 9" Western Larch bears N 75° W, 18.8 feet, scribed "WB/473 BT" on a single blaze.

Office of County Surveyor..... County of Umatilla.....
 State of Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 13th day of September, 1989
 David H. Reubens (COUNTY OFFICIAL) by Kathleen K. Amabeau (DEPUTY)

RECORDED BY
 Dennis L. Gaylord
 Date 8-89
 Book 89
 No. 89-89-R