

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


1-7

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

Set a fir post 3 ft long 3 ins square 24 ins in ground for 1/4 sec cor marked 1/4 S on W face from which:

- A Tamarack 18 ins dia brs S60°W 10 lks dist marked 1/4 S BT
- A Tamarack 18 ins dia brs N80°E 15 lks dist marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.
Description of corner evidence found:

Found a 14 inch diameter Tamarack N80°E, 15 lks dist dead and standing with blaze evident.

Found a 14 inch diameter Tamarack stump S60°W, 10 lks dist, blaze evident. I opened and found scribes.

See map of survey dated August, 1987.

Description of monument and accessories established to perpetuate the original location of this corner: At record bearing and distance from the found bearing trees, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New BTs:

- A 12 inch diameter Spruce bears N53°E, 45.03 feet marked 1/4 S28 BT
- A 5 inch diameter Lodgepole Pine bears N72°W, 26.36 feet marked 1/4 S29 BT

Raised a mound of stone around monument 2 ft. base to top of cap.

I painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

Set a steel fencepost approximately 5 feet West with 54-9 and 54-2 signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 16, 1987.

Witnesses: Greg Blackman, Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 14th day of August, 1987
David H. Chamberlain by Kathleen Chamberlain
 (COUNTY OFFICIAL) (DEPUTY)

87-470