


History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

Set basalt stone 16x13x12 ins 11 ins in the ground for cor of secs 4, 5, 32 and 33 marked with 4 notches on E and 2 notches on W edges from which:

A Pine 10 in diam bears N62°E 55 lks dist marked T6S R33E S33 BT
A Fir 10 in diam bears S60°E 88 lks dist marked T7S R33E S4 BT
A Fir 10 in diam bears S47°W 15 lks dist marked T7S R33E S5 BT
A Pine 20 in diam bears N15°W 56 lks dist marked T6S R33E S32 BT
Corner remonumented in 1977 by Craig L. Wanless, BLM Group no. 350. His notes state:
The cor of secs 4, 5, 32 & 33, on the S bdy of the Tp., determined at record bearing and distance from the only remaining bearing tree; A pine 30 ins diam, bears N15°W, 56 lks dist with scribes visible. At the corner point set an iron post with brass cap marked: (markings shown below) from which new bearing trees: A grand fir 13 ins diam bears N56°E 160 lks dist marked T6S R33E S33 BT. A grand fir 10 ins diam bears S9°E 30 lks dist marked T7S R33E S4 BT. A grand fir 9 ins diam bears S55°W 20 lks dist marked T7S R33E S5 BT.
No record of subsequent monumentation found in Umatilla County survey records.



Description of corner evidence found:


Found a standard BLM brass cap monument marked as shown below:

BLM BTs:

- Found a 11 inch diameter Grand Fir N56°E, 160 lks dist, live and sickly with blaze evident.
Found a 13 inch diameter Grand Fir S9°E, 30 lks dist, live and sickly with scribes visible.
Found a 10 inch diameter Grand Fir S55°W, 20 lks dist, live & sickly, scribes visible.
Found a 11 inch diameter Grand Fir N65°W, 21 lks dist, live and sickly with scribes visible.

Original BT:

- Found a 30 inch diameter Pine N15°W, 56 lks dist, live and vigorous with scribes visible.



Description of monument and accessories I established to perpetuate the

original location of this corner: From the existing found BLM brass cap monument:

New BTs:

- A 9 inch diameter Western Larch bears N12°E, 61.25 feet marked T6S R33E S33 BT
A 5/8" x 30" iron pin with plastic cap marked BGA SURVEY MARKER bears S45°E, 12.13 feet
A 30 inch diameter Ponderosa Pine bears S18°W, 14.69 feet marked T7S R33E S5 BT

Set a steel fencepost approximately 5 feet North with 54-4 and 54-2 signs attached.

I painted a 6 inch red band around all BTs and attached 54-3 and 54-4 signs.

I hereby certify that the above corner point was perpetuated as hereon described on July 22, 1987.

Witnesses: Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept. County of Umatilla
State of OR, I hereby certify that the within instrument was filed in this office for record on the 22nd day of August, 1987.
David H. Kumbel (COUNTY OFFICIAL) by Kathleen Kumbel (DEPUTY)

87-47-P