

USDA-FOREST SERVICE
Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No. **Tower Unit**


Cor.
No. **AP-621**

T. 6 S. R. 34 E.
Merid. Willamette

R.D. North Fork John Day
N.F. Umatilla

County Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar with a 3 1/4" aluminum cap, projecting 1" out of the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

8" Lodgepole Pine Snag, S. 48 E., 34.1 feet, with burnt out double blaze.
6" Western Larch Snag, S. 61 1/2 W., 42.8 feet, with burnt out double blaze.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the Winom Creek crossing on road 52 travel southwesterly on road 52 approx. 0.45 miles to spur ridge on the north side of the road. Ascen spur ridge approx. 200 feet to the corner.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
10/28/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 36" rebar with red plastic cap stamped "UMATILLA N.F." set 33" in the ground, S. 89 3/4 E., 17.55 feet.

RM, 5/8" X 36" rebar with yellow plastic cap stamped "UMATILLA N.F." set 30" in the ground, N. 11 3/4 W., 20.9 feet.

Work Done By D. Schlaich Title Land Surveyor Date 10/28/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No. T. R. M. Willamette Tract or Survey No. Tower Unit Cor. AP-621

Index

File No.

T. 6 S. R. 34 E.
Merid. WILLAMETTE


CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

R.D. NFJD County UMATILLA
N.F. UMATILLA State OREGON

Tract or
Survey No. Tower Unit

Cor.
No. AP-621

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,481,211.75'

Y: 498,608.36'

Datum: NAD1927

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the Winom creek crossing on road 52 travel southwesterly on road 52 approx. 0.45 miles to spur ridge on the north side of the road. Ascend spur-ridge approx. 200 feet to the corner which is located on the spur ridge.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

08-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS TOWER UNIT AP-621 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

7" Western Larch, S. 62° W., 43.1 ft., mkd. "WB/621""BT" on double blaze.

8" Lodgepole Pine, S. 48° E., 34.1 ft., mkd. "WB/621""BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date 08-1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Tower Unit

Cor.

AP-621